

7x12 FIBER SPLICING

Rugged and durable fiber optic splicing trailers specifically designed for the extreme demands that are seen in the telecom industry. The clean, temperature controlled environment has a unique lab layout that allows your technician to maximize productivity in the field.

CHASSIS

- Aluminum Frame
- Dexter Torsion Axle
- 7-Way Trailer Plug
- 5,000 lb Manual Jack
- Adjustable Pintle

ELECTRICAL

- 5.5KW Gas Generator
- Remote Start
- Automatic Transfer Switch
- 50 Amp Load Center
- 60 Amp Converter/Charger
- 12v Deep Cycle Battery
- 12v Cut-Off Switch
- 25' Motorbase Shore Cord

EXTERIOR

- White FRP Sidewalls
- (2) 24" Entrance Doors
- Lighted Directional Arrow Board
- Roof Mounted Strobe Light
- (2) Quartz Flood Light
- Spare Tire with Exterior Mount
- Exterior Cone Holder

INTERIOR

- (2) Cable Access Door with Brushes
- (2) Cable Clamps
- (2) Tinted Slider Windows
- 13,500 BTU Air Conditioner
- 5,200 BTU Electric Wall Heater
- 12v Roof Vent
- CO Detector Hardwired
- (6) 120V Outlets
- (1) 12V Outlet
- Eye Wash Station



GVWR	LENGTH	WIDTH	INTERIOR	CABLE CLAMPS	GENERATOR	COOLING	HEATING	LIGHTING
7,000 lbs	144"	84"	82"	2	5.5KW	13,500 BTU A/C	5,200 BTU Electric	LED

